

RCI **ELECTRIC**

Residential Commercial Industrial

QUOTATION

To: Randy Kurtty/ City of Foley
JOB: Centennial Tower Seasonal Lights
DATE: 06/02/15

RCI Electric LLC, appreciates the opportunity to quote the installation of receptacles atop the clock tower. All work will be completed in accordance with the NEC electrical code, as well as state and local codes.

Scope of Work:

- 1) Use the existing electrical circuit that is located in the southeast column of the clock tower.
- 2) Install receptacles on (4) corners atop of the clock tower to supply seasonal lighting.
- 3) Install circuit wiring from the southeast column to the receptacles atop clock tower.
- 4) Install a dusk to dawn photo cell to control the receptacle power.

Total Bid: \$ 975.00

Note: Any deviation of the described work and material will need to be discussed as a change order.

Sincerely,

Billy N. Taylor

10195 Pineview Dr West | Foley, AL 36535
P: 251.943.2169 | F: 251.943.3119
rci@rcielec.com | rcielec.com

RCI **ELECTRIC**

Residential Commercial Industrial

QUOTATION

To: Randy Kurtts
JOB: City of Foley, Heritage Park Tree Lights #1
DATE: 06/11/15

RCI Electric LLC appreciates this opportunity to submit a quote for the installation of a receptacle that will be located on the northeast corner of the water fountain pavers. The installation work would be completed according to the NEC electrical code, as well as state and local codes.

Scope of Work:

- 1) Install (1) 20 amp, 120 volt receptacle circuit approximately 100 feet in length. The circuit will come from a existing panel to the tree behind the concrete bench on the northeast corner of the water fountain facing highway 59.

Total Bid: \$ 1,275.00

Note: Any deviation from the above scope of work would need to be discussed as a change order.

Thank you,

Billy N. Taylor



QUOTATION

To: Randy Kurtts
JOB: City of Foley, Heritage Park Tree Lights #2
DATE: 06/11/15

RCI Electric LLC appreciates this opportunity to submit a quote for the installation of receptacles to be located on each side of south entrance. The installation work would be completed according to the NEC electrical code, as well as state and local codes.

Scope of Work:

- 1) Install (2) 20 amp, 120 volt receptacle circuits approximately 300 feet in length. To be located on each side of the south entrance which faces the post office.

Total Bid: \$ 2,975.00

Note: Any deviation from the above scope of work would need to be discussed as a change order.

Thank you,

Billy N. Taylor