

City of Foley

Date: February 25, 2013

Project: Streetscapes (revised 3-22-13)

Re: Alston St between Verbena and Jessamine –

Recommendations and cost to complete landscape and irrigation

From: John Graham – Horticulture

This information begins on Alston St south in front of the Fire Station and moves north to the Planning and Zoning building.

Alston / Verbena

- NE corner
- Irrigation
- Live Oak (1)
- Root barrier
- Asiatic Jasmine (300)
- Mulch 2 CY

(2) Islands across from Fire Station

- Irrigation
- Live Oak (2)
- Root barrier
- Azaleas (24)
- Mulch 2 CY

(2) Islands in front of Alston St Market and Middleton Law Firm

- Irrigation
- Live Oak (2)
- Root barrier
- Azaleas (24)
- Mulch 2 CY

Alston / Myrtle Ave

- SE corner
- Irrigation
- Jasmine (300)
- Root barrier
- Mulch 2 CY
- SW corner – same as above
- NW corner
- Irrigation
- Live Oak (1)
- Root barrier
- Mulch 2 CY

NE corner
Irrigation
Jasmine (50)
Root barrier
Mulch 2 CY

(2) Islands on Myrtle across from Goodyear

Irrigation
Azaleas (24)
Mulch 2 CY

(1) Island in front of Paul's Barber Shop

**Fire Hydrant in this location no tree recommended
Irrigation
Dwarf Azaleas (10)
Mulch 1 CY

*** (6) Existing Live Oaks on Alston St between Orange and Myrtle

Consider steel edging and mulch (\$1,100 material cost) for all 6

Alston / Orange

SW corner
Irrigation
Jasmine (100)
Mulch 2 CY

SE corner
Irrigation
Jasmine (30)
Root barrier
Mulch 2 CY

NE corner
Root barrier

NW corner
**Fiber optic hub – no tree recommended
Jasmine (120)
Mulch 2 CY

(4) Small islands between Orange and Laurel

Crape Myrtle (4)
Mulch 2 CY

(2) Islands between Laurel and Jessamine

- Irrigation
- Crape Myrtle (2)
- Azaleas (20)
- Mulch 1 CY

Alston / Jessamine

- NE corner
 - Irrigation
 - Root barrier
 - Jasmine (200)
 - Mulch 2 CY

- NW corner
 - Irrigation
 - Jasmine (50)
 - Mulch 1 CY

- SW corner
 - Remove sod
 - Irrigation
 - Jasmine (200)
 - Live Oak (1)
 - Root barrier
 - Mulch 2 CY

- SE corner
 - Remove sod
 - Irrigation
 - Root barrier
 - Jasmine (200)
 - Mulch 2 CY

Area outside of sidewalk on Myrtle adjacent to used car lot

- Grading and prep work
- Low retention wall
- Irrigation
- Groundcover

Pricing:

Contractor Services

Myrtle - Irrigation, retention wall, grading and prep for Southern Maintenance not to exceed \$1,500

Irrigation for Southern Maintenance to install on all new light poles is quoted for 9 poles is \$3552

Irrigation for Southern Maintenance to install in all beds is quoted at \$13,735

Root barrier for Southern Maintenance to install below irrigation trenches quoted at \$2,676

Total contractor services: \$21,463

Material Costs

(7) Live Oaks 12-14' \$85 each \$595

(6) Crape Myrtles 10-12' \$65 each \$390

(1,550) Asiatic Jasmine 4" pots .75 each \$1,162.50

Root barrier approx. \$4/LF \$3,840

(31) CY Mulch approx. \$25/ CY \$775

Steel edging and mulch for the (6) existing Live Oaks between Orange and Myrtle \$1,100

Total cost to complete: \$29,325.50

***Notes:

All beds will require topsoil and preparations

All new trees will have an individual irrigation bubbler installed

All other irrigation will be 12" spray heads

Azalea beds will be a mix of medium and dwarf cultivars to create step down appearance

Colors will vary