



**BUILDERS**  
CONSTRUCTION MANAGER  
BUILD WITH THE BEST

Phone (251) 943-1112

220 W. Laurel Ave, P.O. Box 669  
Foley, AL 36536

Fax (251) 943-1109

## PROPOSAL

Submitted to: City of Foley  
Attn. Randy Kurtts

Date: August 10, 2018

Dear Mr. Kurtts,

Thank you for requesting a proposal for repair work at the sidewalks on the Northwest corner at the intersection of Highways 98 and 59 (Laurel Ave and McKenzie St.). We propose to furnish all labor, equipment and materials to construct the work as discussed and marked on site and detailed on the below scope of work:


- Remove approximately 940 square feet of existing sidewalks and haul off of all debris; saw cuts offset next to adjacent building walls and at joints to remaining sidewalk areas as needed
- Place and finish new concrete sidewalks at removed areas above with 3,000 psi strength concrete
- Reinstall one existing handicap parking sign and post
- Remove curb from sidewalk to gutter next to planter bed at corner along highway 59 and remove approximately 150 square feet of adjacent asphalt parking area (one half of marked parallel parking space and remaining half to be hatch painted by Owner)
- Place approximately 28 lineal feet of new 6" wide reinforced concrete curb to enclose new widened planter area from removed asphalt area; curb to be flush with sidewalk and taper up to 6" height and tie in to remaining curb where meets gutter
- Place new concrete finish surface product on approximately 120 square feet of existing concrete surfaces that remain between new sidewalk areas

**Cost: \$17,108.00**

Included in costs above is all necessary insurance and licenses.

This proposal is good for 30 days. Thank you for the opportunity to work with you on this project.

Respectfully submitted,

  
John W. Jurkiewicz  
E-J Builders, Inc.