



**JOB NAME: Foley Elementary @ Rose Ave
Open Ditch**

ITEM NO.	ITEM DESCRIPTION	EST QTY	UNIT MEA	UNIT PRICE	TOTAL BID PRICE
1	New Section of Sidewalk	800	SF	\$ 10.00	\$ 8,000.00
3	Doweling new concrete every 16'	5	SF	\$ 14.00	\$ 70.00
43	Sod	135	SF	\$ 6.00	\$ 810.00
44	ADA Detectable Warning Pads 2x4	1	EA	\$ 822.00	\$ 822.00
45	Demolition of Existing 24" Headwall	1	EA	\$ 1,786.00	\$ 1,786.00
45	24" Vertical Headwall	1	EA	\$ 7,250.00	\$ 7,250.00
45	Aluminum Handrail	30	LF	\$ 175.00	\$ 5,250.00
TOTAL AMOUNT BID					\$ 23,988.00

Notes: City to slope from sidewalk to existing ground.
Material to be disposed in City pit.

Drainage & Inlets

ITEM NO.	ITEM DESCRIPTION	EST QTY	UNIT MEA	UNIT PRICE	TOTAL BID PRICE
1	New Section of Sidewalk	830	SF	\$ 10.00	\$ 8,300.00
3	Doweling new concrete every 16'	5	SF	\$ 14.00	\$ 70.00
7	Transition Box	2	EA	\$ 6,000.00	\$ 12,000.00
43	Sod	135	SF	\$ 6.00	\$ 810.00
44	ADA Detectable Warning Pads 2x4	1	EA	\$ 822.00	\$ 822.00
45	Demolition of Existing 24" Headwall	1	EA	\$ 1,786.00	\$ 1,786.00
45	12" ADS	200	LF	\$ 81.00	\$ 16,200.00
45	24" RCP with Concrete Collar	8	LF	\$ 395.00	\$ 3,160.00
45	Aluminum Handrail	30	LF	\$ 175.00	\$ 5,250.00
TOTAL AMOUNT BID					\$ 48,398.00

Notes: 12" ADS maximum pipe size for transition box on upstream side to function.
Transition box at Rose ave will have knock for flow the enter from the west.
Transition box upstream in a 4 way pedestal weir.
Material to be disposed in City pit.