



City of Foley, AL

407 E. Laurel Avenue
Foley, AL 36535

Signature Copy

Resolution: 25-1045-RES

File Number: 25-0063

Enactment Number: 25-1045-RES

A Resolution to Approve Funding for Pilgrim Street Extension and Permission to Go to Bid.

WHEREAS, Pilgrim is a planned City constructed road project for FY24 that has gone into FY25, AND

WHEREAS, Pilgrim design was changed to include an all purpose walking path for an additional \$2,200.00, AND

WHEREAS, the Street Department is requesting \$600,000.00 under Account #400-3010-5100 CR-9, AND

WHEREAS, the Street Department seeks permission to go to bid for the asphalt surfacing and masonry work.

NOW THEREFORE BE IT RESOLVED that the City Council of the City of Foley, Alabama, as follows:


SECTION 1: Appropriates \$600,00.00 under account #400-3010-5100 CR-9.

SECTION 2: Approves permission for Street Department to go to bid for the asphalt paving component and masonry work of the road building project.

SECTION 3: This Resolution shall become effective immediately upon its adoption as required by law.

PASSED, APPROVED AND ADOPTED this 17th, day of February, 2025.

President Signature



Date

2-17-25

Attest by City Clerk



Date

2-17-25

Mayor Signature



Date

2-17-25

Cost Estimate

City of Foley
Pilgrim Street Extension

E. Jackson to E.
Michigan
Road Extension

January 2025

ITEM #	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
206-C1	REMOVAL OF CONCRETE	SY	64	\$7.00	\$ 448.00
206-E1	REMOVAL OF DRAINAGE STRUCTURE	EA	1	\$800.00	\$ 800.00
210-A1	UNCLASSIFIED EXCAVATION	CY	3,950	\$11.50	\$ 45,425.00
210-D	BORROW EXCAVATION,STRUCTURAL FILL (1'-8" MIN.) (A-2-4)	CY	3,163	\$25.00	\$ 79,075.00
301-A1	AGGREGATE BASE COURSE, TYPE B, 6" THICK	SY	3,350	\$30.00	\$ 100,500.00
424-A	1-1/4", SUPERPAVE BITUMINOUS CONCRETE WEARING SURFACE, 1/2" MAX. AGGREGATE SIZE MIX, ESAL RANGE B, 138 LB/SY	TONS	200	\$145.00	\$ 29,000.00
424-C	1-1/2" BITUMINOUS BINDER LAYER (165 LB/SY)	TONS	220	\$155.00	\$ 34,100.00
623-A	CONCRETE DRIVEWAY APRON 6" THICK	SY	46		
623-A	CONCRETE CURB & GUTTER, R-3 ROLL TYPE CURB (30")	LF	2,463	\$48.00	\$ 118,224.00
618-A	5' WIDE CONCRETE SIDEWALK	SY	695	\$85.00	\$ 59,075.00
533-B1	18" RCP STORM DRAIN	LF	429	\$85.00	\$ 36,465.00
533-B2	18" X 11" RCAP STORM DRAIN	LF	89	\$75.00	\$ 6,675.00
533-B3	22" X 14" RCAP STORM DRAIN	LF	68	\$85.00	\$ 5,780.00
533-B4	36"X22" RCAP STORM DRAIN	LF	58	\$115.00	\$ 6,670.00
619-A	CONCRETE SLOPE PAVED HEADWALL	EA	10	\$1,200.00	\$ 12,000.00
600-A	MOBILIZATION	LS	1	\$20,000.00	\$ 20,000.00
206-D1	REMOVAL OF PIPE	LF	100	\$15.00	\$ 1,500.00

405	TACK COAT	SY	2,650	\$2.00	\$ 5,300.00
206-A	SAWCUT EXISTING ASPHALT	LF	140	\$8.00	\$ 1,120.00
660-D	REMOVAL OF TREES	EA	14	\$2,500.00	\$ 35,000.00
660-E	EXISTING GRAVEL REMOVAL	SY	800	\$12.00	\$ 9,600.00
660-F	EXISTING RIP RAP REMOVAL	SY	8	\$100.00	\$ 800.00
665-J	SILT FENCE, TYPE "A"	LF	2,350	\$6.50	\$ 15,275.00
665-I	INLET PROTECTION DEVICES	EA	4	\$65.00	\$ 260.00
665-Q	WATTLES	EA	4	\$75.00	\$ 300.00
665-R	50'X20' CONSTRUCTION ENTRANCE	EA	2	\$2,500.00	\$ 5,000.00
621-A	DOUBLE "S" INLET	EA	2	\$7,500.00	\$ 15,000.00
621-B	SINGLE "S" INLET	EA	2	\$5,000.00	\$ 10,000.00
252-A	SEEDING/MULCHING	AC	1.0	\$2,750.00	\$ 2,750.00
654-A	SOLID SODDING	SY	900	\$7.00	\$ 6,300.00
650-A	TOP SOIL	CY	260	\$42.00	\$ 10,920.00
999-X	WORK OF SIMILAR NATURE	LS	1	\$15,000.00	\$ 15,000.00
TOTAL					\$ 688,362.00