

# ESTIMATE

**Harris Stone Works LLC**

20620 Lawrence Rd  
Fairhope, AL 36532

**City Of Foley**

251-424-8275

Phone: 251-716-2787

Email: harrisstoneworks@gmail.com

Estimate #

000791

Date

05/11/2015

| Description                                                                                                                                                                                                                                                                                                              | Total       |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|
| <b>Field Pavers</b><br>Excavate to proper sub grade.<br>Install 4"-6" limestone base ( 20 tons).<br>Install concrete sand to be used as leveling bed (6tons)<br>Install 800 sft of filter fabric.<br>Install 800 sft of clay pavers.<br>Polymeric sand will fill all paver joints.                                       | \$11,327.01 |
| <b>Banding &amp; Borders</b><br>Excavate to proper sub grade.<br>Install 420 sft of filter fabric under base material.<br>Install 4"-6" limestone base(10tons)<br>Install concrete sand for leveling bed (3.5tons).<br>Install 420 lft of clay pavers in a 12" application.<br>Polymeric sand will fill all paver joints | \$5,498.81  |
| <b>Bench Areas</b><br>Install 8, 6'x8' bench pads.<br>Each pad will cost \$718.60                                                                                                                                                                                                                                        | \$5,748.80  |
| <b>Mobilization</b><br>This is based on a one time mobilization.<br>If HSW was to mobilize due to contractor.<br>An additional charge would occur for each move.                                                                                                                                                         | \$300.00    |
| <hr/>                                                                                                                                                                                                                                                                                                                    |             |
| <b>Subtotal</b>                                                                                                                                                                                                                                                                                                          | \$22,874.62 |
| <b>Total</b>                                                                                                                                                                                                                                                                                                             | \$22,874.62 |