



January 2017
Misc. Drainage Improvements
Scope of Work and Cost Estimate

A min-excavator will be rented and cost shared for both projects

Library

Item

- 1 Remove irrigation pipe as required-Parks
- 2 Excavate along east wall-PW
- 3 Remove shrubs adjacent to building along north wall to mechanical slab-PW
- 4 Using flat point shovel, remove remaining dirt against brick and concrete footing-PW
- 5 Wash clean area to receive coating and blow dry-Maint
- 6 Apply coating to area and apply 2nd coat-Maint
- 7 Place removed topsoil and construct swale-PW
- 8 Re-install irrigation pipe-Parks
- 9 Fine grade and place sod- Horticulture

Cost Estimate

Share mini	\$485
Coating	\$116
Supplies	\$ 30
Sod-1 pallet	\$120
Total	\$751

Baldwin Mutual

A temp construction permit is signed. Work performed by Public Works Dept.

Item

- 1 Sawcut asphalt walking path.
- 2 Excavate trench for drainage pipe/structure.
- 3 Construct drainage box and place pipe.
- 4 Backfill as required.
- 5 Grade area for drainage.
- 6 Place sod

Cost Estimate

Share mini	\$485
Pipe	\$330
Box & grate	\$350
Sod-2 pallets	\$240
Total	\$1,405