



Memo

To: Randy Kurtts, City of Foley
From: Jim Jurkiewicz, E-J Builders, Inc.
Date: November 6, 2019
Re: Heritage Park Pavilion Steps
Request for Change in the Work

You have requested the following work which will result in change of work scope and cost change as follows:

- Remove existing curved rails from concrete embed, store rails off site, demo existing landing slab, haul off and dispose.

ADD: \$1,347.00

- Increase size of south landing walkway to 39'x23'-6", includes excavation, compacted b-base backfill, brick paver edging, increase slab depth to 6" in lieu of 4", install additional #5 reinforcing steel, saw cut contraction joints, seal concrete.

ADD: \$6,521.00

- Change step sub-structure to formed and poured in place solid concrete steps to be faced with brick in lieu of CMU sub-structure, provide additional 216 special water table brick to match job requirements.

ADD: \$1,115.00

- Alternate One: Remove 2 decorative rail sections to storage, layout and core drill 4 holes in reinforced concrete slab, install 4 owner furnished step handrails using non-shrink grout. Paint handrails 2 coats rust resistant white, remove and install new end panels on column base where rail support shafts are welded to columns, repaint 2 column bases and touch up others where decorative rails were removed. NOTE: this work will need to be completed after step work is complete.

ADD: \$2,024.39

\$11,007.39

* Above costs include performance bond costs. Thank You