



Taylor Davis <tdavis@cityoffoley.org>

Justice Center Flume

Jones, Micah <micah.jones@volkert.com>
 To: Taylor Davis <tdavis@cityoffoley.org>

Fri, Oct 10, 2014 at 9:26 AM

SUMMARY OF QUANTITIES				UNIT COST	EXTENSION
QTY	ITEM #	UNIT	DESCRIPTION		
1	201A000	LS	CLEARING AND GRUBBING	\$ 1,000.00	\$ 1,000.00
1	206G002	LS	REMOVAL OF RUBBLE	\$ 20,000.00	\$ 20,000.00
360	210A000	CY	UNCLASSIFIED EXCAVATION	\$ 12.00	\$ 4,320.00
100	210D021	CY	BORROW EXCAVATION (LOOSE TRUCKBED MEASUREMENT)(A-4 OR BETTER)	\$ 15.00	\$ 1,500.00
1	600A000	LS	MOBILIZATION	\$ 6,000.00	\$ 6,000.00
100	610A003	SY	LOOSE RIPRAP, CLASS 2, 18" THICK	\$ 80.00	\$ 8,000.00
45	614A000	CY	SLOPE PAVING	\$ 450.00	\$ 20,250.00
75	650A000	CY	TOPSOIL - 4" THICK*	\$ 15.00	\$ 1,125.00
0.10	652A100	AC	SEEDING *	\$ 2,000.00	\$ 200.00
0.10	656A010	AC	MULCHING	\$ 2,000.00	\$ 200.00
380	654A000	SY	SOLID SODDING *	\$ 5.00	\$ 1,900.00
550	665A-000	LF	SILT FENCE, TYPE A	\$ 6.00	\$ 3,300.00
25	665Q002	LF	12" WATTLES	\$ 12.00	\$ 300.00
1	680A000	LS	ENGINEERING CONTROLS	\$ 2,500.00	\$ 2,500.00
215	610D003	SY	FILTER BLANKET, GEOTEXTILE	\$ 6.00	\$ 1,290.00
35	430B040	TON	AGGREGATE SURFACING (CRUSHED AGGREGATE BASE, TYPE B)	\$ 50.00	\$ 1,750.00

TOTAL # 73,635