

# N'Stride Services , LLC.

109 S Alston St.  
Foley, AL 36535  
251-504-7824  
nstride@live.com

# Estimate

Date	Estimate #
6/11/2018	018-19

Bill To
City of Foley Randy Kurtts 200 N Alston Street Foley AL 36535

Worked To Be Performed At

Item	Description	Cost
Rotten Wood Repair	Remove and replace 105 sq ft of 1 X 3 bead board siding on the north side gable end. Remove and replace 16 feet of 1 X 12 fascia (rotten in two areas). Remove and replace top and corner trim. Cut shingles back over flashing before installing siding to prevent water wicking into bottom of siding. Double prime siding before installing.	2,500.00

I approve the work listed on this estimate only. Any add-ons will be listed on a seperate estimate.	Signature	<b>Total</b>	\$2,500.00
---	-----------	--------------	------------

**We appreciate your business!!!!**