

CHANGE ORDER #1

N'Stride Services , LLC.

109 S Alston St.
Foley, AL 36535
251-504-7824
nstride@live.com

Estimate

Date	Estimate #
7/9/2018	018-20

Bill To
City of Foley Randy Kurtis 200 N Alston Street Foley AL 36535

Worked To Be Performed At
ART CENTER

Item	Description	Cost
Rotten Wood Repair	Replace 84 additional sq ft of 1/2 inch OSB sheathing with 15/32 plywood.	672.00
Rotten Wood Repair	Add 32 feet of 2X4 framing where deteriorated framing was found around windows. See pictures.	225.00
Carpentry	Reset ramp framing away from building and support with 4 X 4 posts. Cut decking boards back 2 inches away from building.	275.00
Misc Repair	Remove garden hose drain from dehumidifier and hard pipe with 1/2 inch PVC.	50.00
Rotten Wood Repair	Replace various small areas of the buildings siding discovered by pressure washing and loosening electrical panel. (35 sq ft)	262.00
I approve the work listed on this estimate only. Any add-ons will be listed on a seperate estimate.		Total \$1,484.00
Signature		

We appreciate your business!!!!